



PHIGENICS ANALYTICAL SERVICES LABORATORY
 1701 Quincy Avenue, Suite 32, Naperville, IL 60540
 Telephone: 630-717-7546 Fax: 630-717-8528 Website: www.phigenics.com

A CDC ELITE Certified Laboratory

Facility Tested: Test Site #1
 Date of Testing: 2013/01/01
 Contact Email: jsmith@email.com

Validation Criteria:
Potable Water - typically in well managed systems, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10³ CFU/ml. Per the OSHA *Legionella* Technical Manual, the viable *Legionella* concentration should be less than 10 CFU/ml unless the water system serves immunocompromised or higher risk users which require a more stringent level of *Legionella* control (less than 1 CFU/ml).
Utility Water (such as cooling water) - typically in well managed systems, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10⁴ CFU/ml. For closed recirculating utility water, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10² CFU/ml. Per the OSHA *Legionella* Technical Manual, the viable *Legionella* concentration should be less than 10 CFU/ml.
 - The facility **Water Management Team** should review all options for Validation Criteria and choose its specific criteria based on the specific systems and users.

Phigenics Validation Test (PVT Premium) Report Summary

Method Used: TimeZero Method, ISO 11731 Spread Plate Method, and PCR

Legionella Caution		Indicates <i>Legionella</i> was detected.
THAB Caution		Indicates total heterotrophic bacteria count exceeds the validation criteria (10 ³ for potable, 10 ⁴ for utility, 10 ³ for closed recirculating utility).
NO Concern	No Shading	Indicates results are better than the validation criteria.
	ND	Indicates <i>Legionella</i> was not detected.
	P	Indicates results are pending.

PASL Number	Date Inoculated	Date Analyzed	Collector	Location Identification	Category (Potable/Utility)	Molecular Marker Neg. Screen	PVT			ISO 11731 Spread Plate			
							Total Bacteria	Lpn S1	Lpn S2-14	Legionella Spp	Lpn S1	Lpn S2-14	Legionella Spp
							CFU/mL						
10000	2013/01/01	2013/01/11	J. Smith	Sink #1 Hot	Potable	Detected	10 ³	70	ND	ND	62	<1	<1
10001	2013/01/01	2013/01/11	J. Smith	Sink #2 Cold	Potable	Not Detected	10 ⁵	ND	ND	ND	<1	<1	<1
10002	2013/01/01	2013/01/11	J. Smith	Sink #3 Hot	Potable	Not Detected	10 ²	ND	ND	ND	<1	<1	<1
10003	2013/01/01	2013/01/11	J. Smith	Sink #4 Cold	Potable	Not Detected	<100	ND	ND	ND	<1	<1	<1
10004	2013/01/01	2013/01/11	J. Smith	Shower #1 Hot	Potable	Detected	10 ³	30	ND	ND	28	<1	<1
10005	2013/01/01	2013/01/11	J. Smith	Shower #2 Cold	Potable	Not Detected	10 ²	ND	ND	ND	<1	<1	<1
10006	2013/01/01	2013/01/11	J. Smith	Shower #3 Hot	Potable	Not Detected	10 ⁴	ND	ND	ND	<1	<1	<1
10007	2013/01/01	2013/01/11	J. Smith	Shower #4 Cold	Potable	Detected	<100	ND	ND	ND	<1	<1	<1
10008	2013/01/01	2013/01/11	J. Smith	Ice Machine #1	Potable	Not Detected	<100	ND	ND	ND	<1	<1	<1
10009	2013/01/01	2013/01/11	J. Smith	Ice Machine #2	Potable	Not Detected	<100	ND	ND	ND	<1	<1	<1
10010	2013/01/01	2013/01/11	J. Smith	Drinking Fountain #1	Potable	Not Detected	<100	ND	ND	ND	<1	<1	<1
10011	2013/01/01	2013/01/11	J. Smith	Drinking Fountain #2	Potable	Detected	10 ²	20	ND	ND	<1	<1	<1
10012	2013/01/01	2013/01/11	J. Smith	Misting System	Potable	Not Detected	10 ⁶	ND	ND	ND	<1	<1	<1
10013	2013/01/01	2013/01/11	J. Smith	Cooling Tower #1	Utility	Detected	10 ⁴	50	ND	ND	10	<10	<10
10014	2013/01/01	2013/01/11	J. Smith	Cooling Tower #2	Utility	Not Detected	10 ⁷	ND	ND	ND	<10	<10	<10
10015	2013/01/01	2013/01/11	J. Smith	Cooling Tower #3	Utility	Detected	10 ⁵	30	ND	ND	50	<10	<10
10016	2013/01/01	2013/01/11	J. Smith	Evaporative Cooler #4	Utility	Detected	10 ⁴	60	ND	ND	70	<10	<10

Disclaimer: Results from the PVT, or from any other analytical protocol for that matter, do not necessarily provide enough evidence to ensure that hazards from pathogenic microorganisms have been eliminated or controlled nor that risk of harm from such hazards has been reduced. Results from the PVT should only be interpreted within the context of properly designed and implemented water management plans. No guarantee regarding results is expressed or implied. THE PVT AND THE RESULTS IT PRODUCES ARE PROVIDED ON AN "AS IS" BASIS. YOU ASSUME TOTAL RESPONSIBILITY AND RISK FOR YOUR USE OF THE PVT AND PHIGENICS IS NEITHER RESPONSIBLE NOR LIABLE FOR ANY DAMAGES ARISING OUT OF YOUR USE OF THE PVT.