



PHIGENICS ANALYTICAL SERVICES LABORATORY
 1701 Quincy Avenue, Suite 32, Naperville, IL 60540
 Telephone: 630-717-7546 Fax: 630-717-8528 Website: www.phigenics.com

A CDC ELITE Certified Laboratory

Facility Tested: Test Site #1
 Date of Testing: 2013/01/01
 Contact Email: jsmith@email.com

Validation Criteria:
Potable Water - typically in well managed systems, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10^3 CFU/ml.
Utility Water (such as cooling water) - typically in well managed systems, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10^4 CFU/ml. For closed recirculating utility water, the total viable heterotrophic aerobic bacterial concentration should be less than or equal to 10^2 CFU/ml.
 - The facility **Water Management Team** should review all options for Validation Criteria and choose its specific criteria based on the specific systems and users.

Phigenics Validation Test (THAB) Analytical Report Summary

Method Used: Total Heterotrophic Aerobic Bacteria

THAB Caution Indicates total heterotrophic bacteria count exceeds the validation criteria (10^3 for potable, 10^4 for utility, 10^3 for closed recirculating utility).
 NO Concern No Shading Indicates results are better than the validation criteria.

PASL Number	Date Inoculated	Date Analyzed	Collector	Location Identification	Category (Potable/Utility)	Category Detail	Total Bacteria CFU/mL
10000	2013/01/01	2013/01/03	J. Smith	Sink #1 Hot	Potable		10^3
10001	2013/01/01	2013/01/03	J. Smith	Sink #2 Cold	Potable		10^5
10002	2013/01/01	2013/01/03	J. Smith	Sink #3 Hot	Potable		10^2
10003	2013/01/01	2013/01/03	J. Smith	Sink #4 Cold	Potable		<100
10004	2013/01/01	2013/01/03	J. Smith	Shower #1 Hot	Potable		10^3
10005	2013/01/01	2013/01/03	J. Smith	Shower #2 Cold	Potable		10^2
10006	2013/01/01	2013/01/03	J. Smith	Shower #3 Hot	Potable		10^4
10007	2013/01/01	2013/01/03	J. Smith	Shower #4 Cold	Potable		<100
10008	2013/01/01	2013/01/03	J. Smith	Ice Machine #1	Potable		<100
10009	2013/01/01	2013/01/03	J. Smith	Ice Machine #2	Potable		<100
10010	2013/01/01	2013/01/03	J. Smith	Drinking Fountain #1	Potable		<100
10011	2013/01/01	2013/01/03	J. Smith	Drinking Fountain #2	Potable		10^2
10012	2013/01/01	2013/01/03	J. Smith	Misting System	Potable		10^6
10013	2013/01/01	2013/01/03	J. Smith	Cooling Tower	Utility		10^4
10014	2013/01/01	2013/01/03	J. Smith	Closed Loop	Utility		10^4

Disclaimer: Results from the PVT, or from any other analytical protocol for that matter, do not necessarily provide enough evidence to ensure that hazards from pathogenic microorganisms have been eliminated or controlled nor that risk of harm from such hazards has been reduced. Results from the PVT should only be interpreted within the context of properly designed and implemented water management plans. No guarantee regarding results is expressed or implied. THE PVT AND THE RESULTS IT PRODUCES ARE PROVIDED ON AN "AS IS" BASIS. YOU ASSUME TOTAL RESPONSIBILITY AND RISK FOR YOUR USE OF THE PVT AND PHIGENICS IS NEITHER RESPONSIBLE NOR LIABLE FOR ANY DAMAGES ARISING OUT OF YOUR USE OF THE PVT.